


LIPAc Control Systems

A Reliability Approach

Alvaro Marqueta

LIPAc Project Team, Rokkasho, Japan






LIPAc -> Linear IFMIF Prototype Accelerator

IFMIF -> International Fusion Materials Irradiation Facility

(the fusion relevant neutron source)




Neutrons in first wall


ITER first wall will present <2 dpa at the end of its operational life

In a Fusion power plant ~150 dpa within 5 years are expected

Existing neutron sources do not provide the needed answers




The first wall of the reactor vessel shall absorb neutrons energy and breed tritium





IFMIF concept




Deuterons at 40 MeV collide on a liquid Li screen flowing at 15 m/s

A flux of $10^{18} \text{ n} \cdot \text{m}^{-2} \cdot \text{s}^{-1}$

is stripped with a broad peak at 14 MeV

Available testing volume and dpa
 High >20 dpa/y in 0.5 liters
 Medium >1 dpa/y in 6 liters
 Low <1 dpa/y in 8 liters

EVEDA Phase: LIPAc




IFMIF/EVEDA

A fruitful Japanese- European International collaboration
(under the Broader Approach Agreement)



EDA phase:

EVA phase:




IFMIF I-EDR

Test Facility



LIPAC




Target Facility




EVEDA phase: LIPAc

Accelerator facility validation

Installed and commissioned in Rokkasho



Rokkasho



IFMIF/EVEDA

A fruitful Japanese- European International collaboration
(under the Broader Approach Agreement)

LIPAc contributions on control systems:



Japanese
implementing agency



European
implementing agency

Central systems:

- Network infrastructure
- Central control system
- Machine Protection system
- Personnel Protection system
- Timing system



(European coordinator)



Local control systems:

- Injector + LEBT
- RFQ
- LLRF
- MEBT
- + (...)

Beam Instrumentation


On-site organization:



Japanese
implementing agency



European
implementing agency




**Integrated Team,
responsible for:**

- Design Verification
- Installation coordination & QA
- Commissioning
- Operation
- Systems maintenance



Overview of LIPAc Control Systems






LIPAc Control System: Main characteristics

- Modular design, following the architecture of the whole LIPAc, based on procurement 'in-kind':
 - independent subsystems with common interface.
- Based on EPICS and CSS for software applications (OPI, archiving, alarms...)
 - common standardized EPICS platform
- Around 20.000 process variables managed globally
 - considered medium size facility
- MPS fastest response (beam shutdown, hardwired loop) of around 20us
 - But also has to manage slower PLC signals


Standard LCS architecture (standalone configuration)

- European contribution, coordinated by CEA
- EPICS standardization through guidelines, common EPICS/CSS platform
- Delivered in local configuration to Rokkasho (to undergo acceptance tests before integration)





LIPAc Schedule






IFMIF Reliability Aspects

IFMIF inherent availability goals

IFMIF Facilities	Availability requirements
Test Facility	96%
Target Facility	94%
Accelerator Facility	87%
Conventional Facilities	98%
Central Control System & Common Instr.	98%
TOTAL (product)	75%

IFMIF




THE INTERNATIONAL FUSION MATERIAL IRRADIATION FACILITY


INTERMEDIATE ENGINEERING DESIGN REPORT

The IFMIF/EVEDA Integrated Project Team

Many thanks to Jose Manuel Arroyo and Enric Bargalló for their superb job on RAMI for IFMIF



Recommended good practices during the design:



LIPAc Ion source operating since November:

- LCS “Successfully” commissioned mid-November (before ownership transfer)
- 3 month stop due to piping improvement in cooling system for safer D+ operation
- Several isolation and multiplexer cards IC damaged
- Modbus modules communication problems
- Old PLC interlocks still in place
- Sometimes software still requires reboot...







When problems appear...


- Documentation not always fully helpful (same with drawings)
- Remote support (+7/8h) limited availability
- Several “black boxes” identified
- Intervention on the delivered control system seems unavoidable

Typical situations in in-kind procurement...

- A trade-off between investment protection (avoid unsafe errors by all means) and availability (avoid spurious triggers as much as possible)
- LIPAc's case: based on experience from J-PARC experiments



- Increase availability by reducing re-arming time after beam shutdown:
 - Directly Inhibiting the timing gate input
 - Valid for RF issues (arcs, reflected power) or BLoM events
 - Avoid reset and rearm by operator, when safety conditions are met
 - Interfaces mostly LLRF, cavities and BLoM







Images from sakura festival at
Hirosaki, Aomori pref.